



Domestic Pack Build Specification:

Rangiora Site

QMPB-002

| 2Frame/SG8 Rough Sawn | | |
|-----------------------|-------|--------|
| | Width | Height |
| 50x25 | 14 | 22 |
| 75x25 | 10 | 22 |
| 100x25 | 7 | 22 |
| 150x25 | 5 | 22 |
| 200x25 | 4 | 22 |
| 150x40 | 5 | 14 |
| 50x50 | 15 | 11 |
| 75x50 | 10 | 11 |
| 100x50 | 7 | 11 |
| 150x50 | 5 | 11 |
| 200x50 | 4 | 11 |
| 250x50 | 3 | 11 |
| 300x50 | 2 | 11 |

| Palings | | |
|---------|-------|--------|
| | Width | Height |
| 150x12 | 7 | 45 |
| 150x19 | 7 | 28 |
| 150x25 | 7 | 22 |

| Posts | | |
|---------|-------|--------|
| | Width | Height |
| 100x75 | 11 | 6 |
| 125x75 | 8 | 6 |
| 100x100 | 11 | 5 |

| 2Frame/SG6/8/10 H1.2 Dry Dressed | | |
|----------------------------------|-------|--------|
| | Width | Height |
| 70x35 | 14 | 17 |
| 140x35 | 7 | 17 |
| 70x45 | 14 | 13 |
| 90x45 | 11 | 13 |
| 140x45 | 7 | 13 |
| 190x45 | 5 | 13 |
| 240x45 | 4 | 13 |
| 290x45 | 3 | 13 |

| 2Frame/SG8 H3 Wet & Dry Dressed | | |
|---------------------------------|-------|--------|
| | Width | Height |
| 70x45 | 10 | 13 |
| 90x45 | 8 | 13 |
| 140x45 | 5 | 13 |
| 190x45 | 4 | 13 |
| 240x45 | 3 | 13 |
| 290x45 | 2 | 13 |

| Decking | | |
|---------|-------|--------|
| | Width | Height |
| 90x19 | 8 | 31 |
| 90x30 | 8 | 17 |

| Retaining Wall | | |
|----------------|-------|--------|
| | Width | Height |
| 185x42 | 4 | 13 |